

thickness of 3.0mm.

2.3 It is recommended that the valve is torqued twice to 27Nm

2.5 It is the users responsibility to ensure that any fluids used

the effect of creep in the clamped joint.

approximately 24 hours between tightenings. This reduces


2.4 A pair of special tools (TM-C1040) are needed to satisfactorily

tighten the valve. The body drive tool has a male 1/2" square spigot and can be mated to a torque wrench. The Housing Adaptor has a 30mm square spigot & can be held in any convenient way.

during installation or operation are compatible with this valve.

For further Information please contact Leafield Marine Limited

OVERALL DIMENSIONS





9, ATWORTH BUSINESS PARK BATH ROAD ATWORTH WILTSHIRE SN12 8SB TEL: 01225 899550

INSTRUCTION SHEET FOR A6 PRESSURE RELIEF VAIVE

OCTOBER 2019			
DRAWING No.	REVISION	SHEET	1
15439	03	OF	1